

कार्यालय नगरपालिका परिषद, बुलन्दशहर
निविदा - सूचना

नगरपालिका परिषद, बुलन्दशहर निम्नलिखित निर्माण कार्यों की अवस्थापना विकास निधि व 12वां वित्त आयोग एवं पालिका निधि के अन्तर्गत निविदायें आमन्त्रित करती है:-

क्र० सं०	कार्य का नाम	अनुमानित लागत	धरोहर राशि	निविदाओं की श्रेणी	निविदा शुल्क	कार्य करने हेतु अवधि
1	वार्ड सं०-2 में आजाद के मकान से हसन, चुक्चान लोधी तक नया खरंजा	335000/-	6700	अनु०जाति / जनजाति	100/-	दो माह
2	निर्माण सी०सी०रोड व नाली वार्ड संख्या - 6 में मौ० राधानगर में के०के० कुमार के मकान से अमर चौधरी के मकान तक	375000/-	7500/-	अनारक्षित	100/-	दो माह
3	कसाई बाड़े के पुल के नीचे पुलिया निर्माण कार्य	151000/-	3000/-	अनारक्षित	100/-	दो माह
4	वार्ड सं०-29, मौ० कसाईबाड़ा, मिर्ची टोला अब्दुल अजीज के पास जीना मरम्मत व कूड़ेदान की मरम्मत का कार्य	108000/-	2200/-	अनारक्षित	100/-	दो माह
5	चौक बाजार की चढ़ाई श्री रामचन्द्र जी महाराज मन्दिर से नाईम के मकान तक वार्ड संख्या - 29	213980/-	4300/-	अनारक्षित	100/-	दो माह
6	निर्माण सी०सी० रोड व नाली, वार्ड सं०-12, कोली वाली गली में मदन मोहन वकील से गुप्ता जी के मकान तक मौ० साठा।	139500/-	2800/-	अनु०जाति / जनजाति	100/-	दो माह
7	वार्ड-15 में मनिहासन भड़भूजों वाली गली, सईद के मकान से मनिहारान चौक तक निर्माण सी०सी० रोड	411000/-	8300/-	अनारक्षित	100/-	दो माह
8	निर्माण सी०सी० रोड नाली, वार्ड सं०-5, सुरेशपाल सिंह से सुन्दर सिंह एडवोकेट तक।	127326/-	2600	अनु०जाति / जनजाति	100/-	दो माह
9	निर्माण वाली व खरंजा मौ० इन्द्रानगर, भूड़ निकट जगन का बाग नरेश यादव वाली गली वार्ड-2	141800/-	2900/-	अनारक्षित	100/-	दो माह
10	शयोरज सिंह एडवोकेट वाली गली, वार्ड संख्या - 9 में सी०सी० रोड व पुलिया	325000/-	6500/-	अनारक्षित	100/-	दो माह
11	मौ० विजय नगर, वार्ड-23 में शंकर लोधी के मकान से विजय नगर रोड तक सी०सी० रोड का कार्य	149000/-	3000/-	अनु०जाति / जनजाति	100/-	दो माह
12	निर्माण सी०सी० रोड व नाली वार्ड-6 में मौहल्ला राधानगर में राजू व मकान से समर सिंह के मकान तक	455615/-	9200/-	अनु०जाति / जनजाति	100/-	दो माह
13	निर्माण सी०सी० रोड व नाली व वार्ड-8, फईमुददीन के मकान से सुनहरी मन्दिर तक	304776/-	6100/-	अनु०जाति / जनजाति	100/-	दो माह
14	निर्माण सी०सी० रोड इण्टरलाकिंग टाईल्स यू-टाईप नाली वार्ड-23 में मौ० कृष्णानगर में चम्पाभवन से प्रेम सिंह के मकान तक सड़क मरम्मत तथा प्रेम सिंह से लक्ष्मी निवासी तक एवं डा० सत्यपाल, रामचरन, श्री कृष्णानगर वाली सहायक गलियों सी०सी० रोड निर्माण कार्य	205153/-	4200/-	अनारक्षित	100/-	दो माह
15	निर्माण नाली व खरंजा जिसे वाली गली व 1 नम्बर गली तक मस्जिद वाली गली वार्ड-8	124277/-	2500/-	अनारक्षित	100/-	दो माह
16	निर्माण नाली खरंजा सुशीला विहार द्वितीय व रामा एन्कलेव के बीच संजीव महेश्वरी के मकान से सोहनपाल सिंह के मकान तक, वार्ड-2	128720/-	2600/-	अनारक्षित	100/-	दो माह
17	निर्माण यू-टाईप, नाली, शिव मन्दिर से श्री बलजीत सिंह के मकान तक व राम मन्दिर, डा० सतीश शर्मा के मकान से होते हुए श्री शयोरज सिंह के मकान तक	685100/-	13800/-	अनारक्षित	200/-	दो माह

	मौ० इन्द्रनगर/मोहननगर, वार्ड सं०-2 में					
	पालिका निधि का कार्य					
18	मौ० कसाईबाड़े पुलि की सीढ़ियों की मरम्मत, वार्ड-30	84770/-	1700/-	अनारक्षित	100/-	एक माह
19	मौ० काजीबाड़ा अन्सारियान की मुख्य गली में सी०सी० टाईल्स निर्माण कार्य, वार्ड-30	457000/-	9200/-	अनु०जाति / जनजाति	100/-	दो माह
20	निर्माण सी०सी० रोड व नाली वार्ड-5, मोहल्ला चांदपुर में स्वामी नेमपाल सिंह के मकान से जी०टी० रो तक	1335500/-	26700/-	अनारक्षित	300/-	तीन माह
	12वां वित्त आयोग के कार्य					
21	मोती बाग में फायर पुलिस स्टेशन के सामने बच्चा पार्क का निर्माण कार्य एवं बच्चों के खेलने के लिए झूले आदि उपकरण एवं प्लांटेशन	920475/-	18500/-	अनारक्षित	200/-	तीन माह
22	निर्माण सी०सी० टाईल्स खरंजा, मौ० गिरधारी नगर, वार्ड संख्या-1 में फौजी पी०सी०ओ० से मोहर सिंह जे०ई० के मकान से होते हुए बलवीर सिंह के मकान तक	254090/-	5100/-	अनारक्षित	100/-	दो माह
23	डी०एम० कॉलोनी के पीछे डा० रवि रञ्जन दत्त, पशु चिकित्साधिकारी के आवास के सामने से ऑफिसर्स क्लब तक निर्माण सी०सी० रोड व इण्टरलाकिंग खरंजा	400385/-	8100/-	अनु० जाति / जनजाति	100/-	दो माह
24	निर्माण सी०सी० रोड व नाली वार्ड सं०-5 ब्रजनन्दन गुप्ता से हरपाल सिंह तक तथा गोपी चन्द ठेकेदार एवं गिरीशपाल एडवोकेट वाली गली में	109540/-	2200/-	अनारक्षित	100/-	दो माह
25	निर्माण सी०सी० रोड व नाली मौ० साठा, वार्ड-12, बिजलीघर के सामने गली नरेन्द्र शर्मा, एडवोकेट वाली	188415/-	3800/-	अनारक्षित	100/-	दो माह

- 1- उपरोक्त निर्माण कार्यों की निविदायें नियत शुल्क का भुगतान करते हुए नगर पालिका परिषद, बुलन्दशहर व अपर जिलाधिकारी (प्रशासन)/प्रभारी अधिकारी (स्था०नि०) एवं उप जिलाधिकारी (सदर) के कार्यालयों पर दिनांक 04.05.2010 को दोपहर 2.00 बजे तक प्राप्त की जा सकेंगी।
- 2- क्रम संख्या 1 ता 16 व 18, 19 22 ता 25 से सम्बन्धित निर्माण कार्यों हेतु निविदायें नगर पालिका परिषद, बुलन्दशहर के कार्यालय में रखे गये निविदा बॉक्स में दिनांक 05.05.2010 को दोपहर 2.00 बजे तक डाली जा सकेंगी। यह निविदायें इसी दिनांक को सांय 3.00 बजे नगर पालिका परिषद, बुलन्दशहर में सक्षम अधिकारी के समक्ष खोली जायेगी।
- 3- क्रम संख्या 17 व 20 एवं 21 से सम्बन्धित निर्माण कार्यों की निविदायें नगर पालिका कार्यालय व अपर जिलाधिकारी (प्रशासन)/प्रभारी अधिकारी (स्था०नि०) एवं उप जिलाधिकारी (सदर) के कार्यालयों में रखे गये निविदा बॉक्स में दिनांक 06.05.2010 को दोपहर 2.00 बजे तक डाली जा सकेंगी। यह निविदायें इसी दिनांक को सांय 4.00 बजे अपर जिलाधिकारी (प्रशासन)/प्रभारी अधिकारी (स्था०नि०) के समक्ष खोली जायेंगी।
- 4- निविदा खोले जाने के समय निविदादाता की उपस्थिति वांछित है।
- 5- सशर्त निविदायें मान्य नहीं की जायेंगी और स्वतः ही निरस्त समझी जायेंगी।
- 6- निर्माण कार्यों से सम्बन्धित अभिलेख सिविल अभियन्ता के कार्यालय में कार्य दिवसों/कार्य समय में देखे जा सकते हैं।
- 7- शासनादेश सं०-425/23-07-2010-25(सा)/2009 दिनांक 25.01.2010 के अनुसार अनुसूचित जाति/जनजाति के ठेकेदारों के लिये पाँच लाख को बढ़ाकर पच्चीस लाख की गई व्यवस्था के अनुसार ही आरक्षण की कार्यवाही उपरोक्तानुसार निविदाओं में की गई है।
- 8- प्रत्येक निविदा के साथ निर्धारित धरोहर राशि की एन०एस०सी०/एफ०डी०आर० अधिशासी अधिकारी, के पद नाम से बंधक को मूल रूप में संलग्न करना अनिवार्य होगा किसी भी दशा में छायाप्रति मान्य न होगी अन्यथा की स्थिति में निविदा अस्वीकार कर दी जायेगी।
- 9- उक्त निविदाओं के सम्बन्ध में निर्माण सामग्री/कार्य कर, व्यापारकर एवं अन्य कर आदि ठेकेदार द्वारा भुगतान करने होंगे।
- 10- प्रत्येक निविदा दाता निविदा देने से पूर्व कार्य स्थल का निरीक्षण कर सकते है।
- 11- केवल विभागीय पंजीकृत ठेकेदार ही पंजीकरण श्रेणी के अनुसार निविदा दे सकेंगे।
- 12- समस्त अथवा किसी भी निविदा को बिना कारण बताये रद्द करने का अधिकार सक्षम अधिकारी/जिलाधिकारी महोदय में निहित होगा।

नगर अभियन्ता
नगर पालिका परिषद,
बुलन्दशहर

अधिकासी अधिकारी
नगर पालिका परिषद,
बुलन्दशहर

कार्यालय, नगर पालिका परिषद, बुलन्दशहर।

अधिकासी अधिकारी,
नगर पालिका परिषद,
बुलन्दशहर।

नगर अभियन्ता,
नगर पालिका परिषद,
बुलन्दशहर।

निविदा पत्र

कार्य का नाम:-

निविदा का मूल्य:- धरोहर राशि -

निविदा आमंत्रण का दिनांक:-

कार्य पूर्ण करने की अवधि:- दो माह

निविदा बिक्रय का दिनांक:-

निविदा खोले जाने का दिनांक:-

वैधता की अवधि-तीन माह

क्रमांक	मद का विवरण	मात्रा	दर	प्रति इकाई
---------	-------------	--------	----	------------

कार्य की बिल आफ क्वान्टीटी साथ में संलग्न है।

मैने/हमनेनिवासी.....

जो इस पालिका में श्रेणी..... वर्ष..... के लिए पंजीकृत ठेकेदार है।

उपरोक्त कार्य/मदों का भलि भांति अध्ययन कर लिया है। अतः मै/हम इस कार्य को आंगणित दरों से

.....(शब्दों में) प्रतिशत उच्च/निम्न/समान दरों पर कार्य करने को तैयार/सहमत हूँ/है। उपरोक्त कार्य

हेतु दो प्रतिशत धरोहर राशि रू० की एन०एस०सी०/एफ०डी०आर० नं० संलग्न कर दी है।

शर्तें

- (1) कार्य का निष्पादन उ०प्र० लोक निर्माण विभाग को विस्तृत विशिष्टियों के अनुरूप कराया जायेगा।
- (2) कार्य में कमी/बढोत्तरी होने पर कोई अतिरिक्त दर की मांग ठेकेदार द्वारा नहीं की जायेगी।
- (3) ठेकेदार किसी भी स्तर तक तकनीकी आडिट सेल या अन्य किसी भी विभागीय उच्चाधिकारी द्वारा यहां तक कि कार्य के पूर्ण होने पर भी कार्य में बतायी गयी कमी के लिए एवं इसके सापेक्ष को जाने वाली वसूली भुगतान के लिए बाध्य होगा।
- (4) सडक निर्माण के समय ठेकेदार सामग्री कार्य स्थल पर चट्टे के रूप में इक्टठा करेगा। सामग्री को माप कराकर अवर अभियन्ता/सिविल अभियन्ता की अनुमति से कार्य शुरू करेगा।
- (5) निविदा, सामग्री की लागत ठेकेदार द्वारा भुगतान की गयी रायलटी, छटनी एवं टेस्टिंग खर्च, सामग्री अस्वीकृत कर दिये जाने पर स्थल से हटाने पर खर्च आदि को सम्मिलित करते हुए होगी।
- (6) निविदा स्वीकृति होने की सूचना प्राप्त होने पर ठेकेदार को नियमानुसार जमानत राशि राष्ट्रीय बचत नियमों के अधीन पत्र अधिकासी अधिकारी के नाम बन्धित कराते हुये स्टाम्प पर एक सप्ताह में अनुबंध करना होगा अन्यथा की स्थिति में अग्रिम राशि जब्त कर निविदा निरस्त कर दी जायेगी।
- (7) किसी भी प्रकार का वाद जो कार्य के विरुद्ध अथवा कारण, किसी बाहरी व्यक्ति द्वारा माननीय न्यायालय में दायर किया जाता है। उसका प्रतिवाद (प्रतिरक्षा) करने एवं उस पर आये व्यय/दण्ड को वहन करने के लिए ठेकेदार बाध्य होगा।

मै प्रमाणित करता हूँ कि मै यह अच्छी तरह जानता हूँ कि उपरोक्त सभी शर्त मानने को बाध्य होऊंगा तथा कार्य को प्रगति अनवरत रखते हुये निर्धारित अवधि में कार्य पूर्ण कर दूंगा।

हस्ताक्षर लिपिक विक्रयकर्ता

हस्ताक्षर ठेकेदार
पता सहित

BILL OF QUANTITY

कार्य का नाम – वार्ड संख्या 2 में आजाद के मकान से हसन, चुक्खन लोधी तक नाली व खरंजा

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	504.00	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	28.80	1550.00	CUM
3	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	52.03	2100.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	326.40	82.00	CUM
5	Laying Kharajan with straight over burnt brick laid on ergo joints filling with local earth .	648.00	145.00	CUM

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम — निर्माण सी0सी0 रोड़ व नाली वार्ड संख्या-6 में मौ0 राधानगर में के0के0 कुमार के मकान से अमर चौधरी के मकान तक।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Dismantling brick work or stone work in mud mortar and including stacking of materials as directed by the engineer in charge.	16.61	39.00	CUM
2	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	180.68	132.00	CUM
3	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	60.23	1550.00	CUM
4	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	17.46	2100.00	CUM
5	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	158.40	82.00	SQM
6	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	48.68	4400.00	CUM
7	Supply and fixing of Marble Stone	ONE	3000.00	NO.
8	Deduct old material	16.61	400	CUM

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम — कसाई बाडे के पुल के नीचे पुलिया निर्माण कार्य।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	23.80	1550.00	CUM
2	M-150 Brick Work in one part Cement and four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	4.20	2100.00	CUM
3	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	19.00	82.00	SQM
4	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	14.00	4400	CUM
5	RCC Work with cement approved coarse sand & 2cm gauge approved stone grit in proportions of 1 : 2 : 4 slab. excluding supply of reinforcement and its bending, but including necessary centering & shuttering etc and supply of all material labour, tool & plants etc S.I.No 284	4.20	4450.00	CUM
6	M.S.(for steel or plain) in plain work such as R.C.C. or R.B. work including bending for proper Shape and including supply of steel & its wastage bend, hook and authorized overlapping shall be measured and including cost of binding wire S.I. No 504	4.94	4130.00	QTL
7	Supply and fixing of Marble Stone	ONE	3000	NO.

BILL OF QUANTITY

कार्य का नाम – वार्ड संख्या 29, मौ0 कसाईबाड़ा मिर्ची टोला ट्राली अब्दुल अजीज के पास जीना मरम्मत व कूड़ेदान की मरम्मत का कार्य।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	0.67	1550.00	CUM
2	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	8.34	2100.00	CUM
3	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	100.00	82.00	SQM
4	Supply and fixing of mild steel channel but in heavy size such as trusses, bulit up gates, record racks roof work gates etc .including riveting or welding where necessary S.I.No 503	6.00	5400.00	QTL
5	RCC Work with cement approved coarse sand & 2cm gauge approved stone grit in proportions of 1 : 2 : 4 slab. excluding supply of reinforcement and its bending, but including necessary centering & shuttering etc and supply of all material labour, tool & plants etc S.I.No 284	2.59	4400.00	CUM
6	M.S.(for steel or plain) in plain work such as R.C.C. or R.B. work including bending	2.54	4900.00	QTL

	for proper Shape and including supply of steel & its wastage bend, hook and authorized overlapping shall be measured and including cost of binding wire S.I. No 504			
7	Supply and fixing white chine glazed tiles (S.I. 628)	30.00	810.00	
8	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – चौक बाजार की चढाई श्री रामचन्द्र जी महाराज मन्दिर से नईम के मकान तक वार्ड संख्या-29

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	26.40	1550.00	CUM
2	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	10.12	2100.00	CUM
3	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	44.00	82.00	SQM
4	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	33.00	4400.00	CUM
5	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer

BILL OF QUANTITY

कार्य का नाम – निर्माण सी0सी0 रोड़ व नाली वार्ड संख्या 12, कोली वाली गली में मदन मोहन वकील से गुप्ता जी के मकान तक मौ0 साठा।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	17.05	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	17.05	1550.00	CUM
3	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	8.56	2400.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	37.20	82.00	SQM
5	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	1.43	3450.00	CUM
6	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	17.05	4400.00	CUM
7	Supply and fixing of mild steel channel but in heavy size such as trusses, bulit up gates, record racks roof work gates etc .including riveting or welding where necessary S.I.No 503	1	4630.00	SQM
8	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – वार्ड-15, में मनिहारान भूड़ भूजों वाली गली सईद के मकान से मनिहारान चौक तक निर्माण सी0सी0 रोड़।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	47.88	1550.00	CUM
2	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	20.98	2100.00	CUM
3	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	96.72	82.00	SQM
4	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	1.15	3450.00	CUM
5	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	59.85	4400.00	CUM
6	Supply and fixing of mild steel channel but in heavy size such as trusses, bulit up gates, record racks roof work gates etc .including riveting or welding where necessary S.I.No 503	3.50	4630.00	SQM
7	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad

BILL OF QUANTITY

कार्य का नाम – निर्माण सी0सी0 रोड़ नाली वार्ड संख्या 5 सुरेश पाल सिंह से सुन्दर सिंह एडवोकेट तक ।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	57.75	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	19.25	1550.00	CUM
3	M-150 Brick Work in one part Cement and three part coarse sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 307 .)	5.82	2400.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	46.20	82.00	SQM
5	Laying of C.C. Road in 1:2:4 cement course sand and stone grid.	15.95	4400.00	CUM
6	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण नाली व खरंजा मौ0 इन्द्रानगर भूड़, निकट जगन का बाग नरेश यादव वाली गली वार्ड-2,

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	480.00	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	5.44	1550.00	CUM
3	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	9.75	2100.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	84.80	82.00	CUM
5	Laying B.O.E. with 1st class bricks (S.I. No. 763)	332.00	155.00	CUM

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – श्यौराज सिंह एडवोकेट वाली गली में वार्ड-9 सी0सी0 रोड़ व पुलियां का निर्माण।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work in execution in foundation In ordinary soil S.I No. 251 (a)	16.20	38.00	CUM

2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	48.96	1550.00	CUM
3	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	15.96	2400.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	126.80	82.00	SQM
5	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	39.00	4400.00	CUM
6	RCC Work with cement approved coarse sand & 2cm gauge approved stone grit in proportions of 1 : 2 : 4 slab. excluding supply of reinforcement and its bending, but including necessary centering & shuttering etc and supply of all material labour, tool & plants etc S.I.No 284	3.24	4450.00	CUM
7	M.S.(for steel or plain) in plain work such as R.C.C. or R.B. work including bending for proper Shape and including supply of steel & its wastage bend, hook and authorized overlapping shall be measured and including cost of binding wire S.I. No 504	3.81	4130.00	QTL
8	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – मौ० विजय नगर वार्ड-23, में शंकर लोधी के मकान से विजय नगर रोड़ तक निर्माण सी०सी० रोड़ का कार्य।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	5.00	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	24.00	1550.00	CUM
3	M-150 Brick Work in one part Cement and three part coarse sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 307 .)	8.84	2400.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	76.80	82.00	SQM
5	Laying of C.C. Road in 1:2:4 cement course sand and stone grid.	18.40	4400.00	CUM
6	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण सी०सी० रोड़ व नाली वार्ड-6 में मौहल्ला राधानगर में राजू के मकान से समर सिंह के मकान तक।

S. N.	Item of Work	Quantity	Rate	Per
-------	--------------	----------	------	-----

1	2	3	4	5
1	Dismantling brick work or stone work in mud mortar and including stacking of materials as directed be the engineer in charge.	25.55	39.00	CUM
2	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	219.00	132.00	CUM
3	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	73.00	1550.00	CUM
4	M-150 Brick Work in one part Cement and four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	21.16	2100.00	CUM
5	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	192.00	82.00	SQM
6	Laying of C.C. Road in 1:2:4 cement course sand and stone grid.	59.00	4400.00	CUM
7	Supply and fixing of Marble Stone	ONE	3000	NO.
8	Deduct old material	25.55	400.00	CUM

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण सी0सी0 रोड़ व नाली वार्ड-8, फाईमुद्दीन से सुनेहरी मस्जिद तक ।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5

1	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	39.52	1550.00	CUM
2	M-150 Brick Work in one part Cement and Four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	23.46	2100.00	CUM
3	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	62.00	82.00	SQM
4	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	3.56	3450.00	CUM
5	Laying of C.C. Road slab 10cm thick in 1:2:4 cement course sand and stone grid.	39.52	4400.00	CUM
6	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण सी0सी0 रोड़ इन्टर लॉकिंग टाईल्स यू0टाईप नाली वार्ड-23, में मौ0 कृष्णा नगर में चम्पा भवन से प्रेम सिंह के मकान तक सड़क मरम्मत तथा प्रेम सिंह से लक्ष्मी निवास तक एवं डा0 सत्यपाल, श्री रामचरन, श्री कृष्ण कुमार वाली सहायक गलियों में सी0सी0 रोड़ निर्माण कार्य ।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all	28.13	1550.00	CUM

	material and all complete work S.I. No. 273.			
2	M-150 Brick Work in one part Cement and three part coarse sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 307 .)	7.77	2400.00	CUM
3	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	126.00	82.00	SQM
4	Laying of C.C. Road slab 10cm thick in 1:2:4 cement coarse sand and stone grid.	30.13	4400.00	CUM

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण नाली व खरंजा जिरों वाली गली व 1 नम्बर गली तक मस्जिद वाली गली वार्ड-8,

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	300.00	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	5.38	1550.00	CUM
3	M-150 Brick Work in one part Cement and four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	9.75	2100.00	CUM

4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	84.80	82.00	SQM
5	Laying kharanja with st. over burnt brick laid on edge joints filling with local earth.	332.00	155.00	CUM
6	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण नाली खरंजा सुशीला बिहार द्वितीय व रामाएन्कलेम के बीच संजीव माहेश्वरी के मकान से सोहन पाल सिंह के मकान तक वार्ड-2,

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	196.88	132.00	CUM
2	Concrete with 4 cm. Gauge Brick ballast finesand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	5.60	1550.00	CUM
3	M-150 Brick Work in one part Cement and four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	23.52	2100.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper	105.00	82.00	SQM

	completion of the work (S.I. No. 583)			
5	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	3.29	3450.00	CUM
6	Laying kharanja with st. over burnt brick laid on edge joints filling with local earth.	140.00	155.00	CUM
7	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण यू0टाईप नाली शिव मन्दिर से श्री बलजीत सिंह के मकान तक व राम मन्दिर, डा0 सतीश शर्मा के मकान से होते हुए श्री श्यौराज सिंह के मकान तक मौ0 इन्द्रानगर/मोहननगर वार्ड-2,

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work in execution in foundation In ordinary soil S.I No. 251 (a)	120.00	38.00	CUM
2	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	120.00	113.50	CUM
3	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	64.00	1550.00	CUM
4	M-150 Brick Work in one part Cement and three part coarse sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 307 .)	161.00	2400.00	CUM
5	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	1040.00	82.00	SQM

6	Supply and fixing of 80 mm thick interlocking cement tiles with the cost of tiles including supply & preading of sand t required template as necessary required for proper completion of work.	11.50	3450.00	SQM
7	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	20.00	3450.00	CUM
8	RCC Work with cement approved coarse sand & 2cm gauge approved stone grit in proportions of 1 : 2 : 4 slab. excluding supply of reinforcement and its bending, but including necessary centering & shuttering etc and supply of all material labour, tool & plants etc S.I.No 284	3.00	4450.00	CUM
9	M.S.(for steel or plain) in plain work such as R.C.C. or R.B. work including bending for proper Shape and including supply of steel & its wastage bend, hook and authorized overlapping shall be measured and including cost of binding wire S.I. No 504	2.59	4130.00	QTL
10	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – मौहल्ला कसाई बाड़े पुल की सीढ़ियों की मरम्मत
वार्ड-20,

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Dismantling brick work or stone work in mud mortar and including stacking of materials as directed be the engineer in charge.	ONE	5000	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in	5.00	1550.00	CUM

	found at on of drain including supply of all material and all complete work S.I. No. 273.			
3	M-150 Brick Work in one part Cement and three part coarse sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 307 .)	3.41	2400.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	57.87	82.00	SQM
5	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	.92	3450.00	CUM
6	Supply and fixing of mild steel railing but in heavy size such as trusses, bulit up gates, record racks roof work gates etc .including riveting or welding where necessary S.I.No 503	7.58	4630.00	SQM
7	RCC Work with cement approved coarse sand & 2cm gauge approved stone grit in proportions of 1 : 2 : 4 slab. excluding supply of reinforcement and its bending, but including necessary centering & shuttering etc and supply of all material labour, tool & plants etc S.I.No 284	2.14	4450.00	CUM
8	M.S.(for steel or plain) in plain work such as R.C.C. or R.B. work including bending for proper Shape and including supply of steel & its wastage bend, hook and authorized overlapping shall be measured and including cost of binding wire S.I. No 504	2.10	4130.00	QTL
9	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – मौहल्ला कांजीबाडा अन्सारियान की मुख्य गली में
सी0सी0 टाईल्स निर्माण कार्य वार्ड-30,

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	103.95	113.50	CUM
2	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	41.58	1550.00	CUM
3	M-150 Brick Work in one part Cement and four part fine sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 305 .)	26.56	2100.00	CUM
4	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	115.50	82.00	SQM
5	P.C.C. 1 : 2 : 4 and all complete. Work (S.I. No. 279 (a))	3.80	3450.00	CUM
6	Supply and fixing of 80 mm thick interlocking cement tiles with the cost of tiles including supply & preading of sand t required template as necessary required for proper completion of work.	519.75	635.00	SQM
7	Supply and fixing of Marble Stone	ONE	3000	NO.

Junior Engineer
Nagal Palika Parishad
Bulandshahr

BILL OF QUANTITY

कार्य का नाम – निर्माण सी0सी0 रोड व नाली वार्ड-5 मौहल्ला चाँदपुर में स्वामी नेमपाल सिंह के मकान से जी0टी0 रोड तक।

S. N.	Item of Work	Quantity	Rate	Per
1	2	3	4	5
1	Dismantling brick work or stone work in mud mortar and including stacking of materials as directed by the engineer in charge.	92.00	39.00	CUM
2	Earth work infilling 6 K.M. Cartage and with cutting S.I No. 261 (b) 253 (a) and 231 (a)A	690.00	113.50	CUM
3	Concrete with 4 cm. Gauge Brick ballast fine sand of 1.25 mm F.M. Module S.I. No. 305 and cement in ratio of 12 : 6 : 1 in found at on of drain including supply of all material and all complete work S.I. No. 273.	184.00	1550.00	CUM
4	M-150 Brick Work in one part Cement and three part coarse sand in foundation including supply of all material, labor, tools & plants etc. required for proper completion of the work (S.I. No. 307 .)	70.10	2400.00	CUM
5	12 MM thick cement plaster with cement & coarse sand in 1:3 over brick work minimum thickness not to be less than 1cm including supply of all material labor, tools & plant etc required for proper completion of the work (S.I. No. 583)	609.50	82.00	SQM
6	Laying of C.C. Road slab 10cm thick in 1:2:4 cement coarse sand and stone grid.	178.25	4400.00	CUM
7	Supply and fixing of Marble Stone	ONE	3000	NO.
8	Deduct Old material	92.00	400.00	CUM

Junior Engineer
Nagal Palika Parishad
Bulandshahr